Tree Protection / Replacement Data Table

Total Site Acreage (Section 2)	29.37
Tree Units Required @ 5 units per acre	**146.8**

Tree Units Provided from Existing Trees

Saved Tree Sizes	Quantity	Units Per Tree	Total Units Per Tree Size
12"	37	1.8	66.6
14"	25	2.1	52.5
16"	9	2.4	21.6
18"	5	2.8	14
20"	5	3.2	16
22"	1	3.6	3.6
24"	1	4.1	4.1
26"	1	4.7	4.7
28"	0	5.3	0
30"	0	5.9	0
32"	1	6.6	6.6
34"	0	7.3	0
36"	0	8.1	0
Total Trees to be Saved	**85**		
Total Units From Trees to Remain			189.7

Trees Proposed	Quantity	Units Per Tree Size	
Street Trees @ 3"		0.5	0
Buffer Yard Trees @ 2"		0.5	0
Buffer Yard Trees @ 3"		0.5	0
Total New Trees Proposed	0		
Total Units From Trees Proposed			0
Total Units From All Trees			**189.7**

Know what's **below.**
Call before you dig.

0 80 160 240

RAGAN•SMITH
LAND PLANNERS • CIVIL ENGINEERS
LANDSCAPE ARCHITECTS • SURVEYORS
NASHVILLE
P.O. BOX 60070
1400 MEMORIAL STREET
NASHVILLE, TN. 37206
(615) 244-8591
CHATTANOOGA
1410 COMMERCE STREET
SUITE 200
CHATTANOOGA, TN. 37402
(423) 490-9400
• www.ragansmith.com •

SUMMERLYN - SECTION 2
FOR
THE JONES COMPANY

TOWN OF NOLENSVILLE, WILLIAMSON COUNTY, TN

JOB NO.	15-074
WK. ORDER:	0253
DESIGNED:	B. SMITH
DRAWN:	K. KORNGOLD
SCALE:	1"=80'
DATE:	JUNE 9, 2015
REVISIONS	

EXISTING TREE PLAN

G:\0253-NOLENSVILLE\ENGINEERING\SECTION 2\PLAN SHEETS\EXISTING TREE PLAN.DWG
PLOTTED BY: TROY P. GARDNER ON: 7/13/2015 9:30 AM LAST UPDATED BY GRG ON: 7/13/2015 12:26 PM